



LIVEPANEL PACK





LivePanel PACK is a green wall system available in four standard dimensions. It is delivered as a ready-made package. This modular green wall system can easily and quickly be converted into a green wall. It is the ideal solution for spaces with one or more smaller wall surfaces. The LivePanel PACK modular green wall system consists of large gutter profiles fitted with a water tank that is filled by hand, and with interchangeable plant cassettes with slots. LivePanel PACK can be fitted to new or existing walls in indoor or outdoor environments. The various sizes and creative plant options available make LivePanel PACK a flexible, space-saving green wall system that can be used in an endless number of ways.

### BENEFITS

- Vertical greenery takes up less space
- Improves the indoor climate and air quality
- Helps improve focus, productivity, and general wellbeing
- Improves the acoustics in a room
- Insulating and sound-dampening effects
- Lowers stress levels

Indoor		Outdoor		
Office	Hotel	Retail	Hospitality	School

### FEATURES

- Manual watering
- Available in four sizes
- No electricity, pump, or water drainage required
- Low water consumption and no waste
- Slim system helps save space
- Interchangeable plant cassettes
- Easy and quick installation
- Fully recyclable
- Total freedom in design and choice of plants

### TECHNICAL INFORMATION

#### DIMENSIONS

LivePanel PACK is a complete green wall system delivered as a package. It is available in four standard dimensions:

2 x 2: 0.87 x 1.09 m (W x H)

2 x 3: 0.87 x 1.57 m (W x H)

3 x 2: 1.27 x 1.09 m (W x H)

6 x 4: 2.48 x 2.06 m (W x H)

#### SURFACE AREA

2 x 2: 0.95 m<sup>2</sup>

2 x 3: 1.37 m<sup>2</sup>

3 x 2: 1.38 m<sup>2</sup>

6 x 4: 5.10 m<sup>2</sup>

#### PLANT CASSETTES & GUTTERS

2 x 2: 4 plant cassettes & 3 gutters

2 x 3: 6 plant cassettes & 4 gutters

3 x 2: 6 plant cassettes & 3 gutters

6 x 4: 24 plant cassettes & 5 gutters

#### GROSS WEIGHT

2 x 2: approx. 36 kg (incl. plants and water)

2 x 3: approx. 53 kg (incl. plants and water)

3 x 2: approx. 53 kg (incl. plants and water)

6 x 4: approx. 210 kg (incl. plants and water)

#### PLANTS REQUIRED (NOT INCLUDED AS STANDARD)

The quantities below are indicative and have been calculated based on nine plants per plant cassette.

2 x 2 : 36 plants

2 x 3 / 3 x 2 : 54 plants

6 x 4 : 216 plants

#### PLANT POT SIZE

Depending on the root system of the plant, Mobilane recommends using plant pots no larger than size 10 (P10) when planting the cassettes.

#### INSTALLATION TIME

The following installation time serves as an indication of how long it takes to install the hardware. This example only reflects the time needed to plant the cassettes:

2 x 2 / 2 x 3 / 3 x 2 : 1 hour

6 x 4 : 2 hour

